



4141 Douglas Drive North • Crystal, Minnesota 55422-1696

Tel: (763) 531-1000 • Fax: (763) 531-1188 • [www.crystalmn.gov](http://www.crystalmn.gov)

## REQUEST FOR PROPOSALS (“RFP”)

### **4343 Xenia Avenue North** **Lot Price \$50,000**

The Economic Development Authority of the City of Crystal (“the EDA”) is requesting proposals from builders to purchase 4343 Xenia Avenue North for construction of a new single family house. Enclosed please find the Proposal Form and Guidelines for making a proposal.

To receive consideration, proposals must be submitted on a completed Proposal Form plus the required attachments and additional information. Incomplete proposals will not be considered. Proposals may be submitted at any time; the first qualifying proposal we receive will be presented to the EDA board, unless the lot has been optioned by another builder.

If you have questions about the RFP process or the enclosed Guidelines, feel free to contact me at 763.531.1142 or [john.sutter@crystalmn.gov](mailto:john.sutter@crystalmn.gov). Thank you for your interest.

Regards,

A handwritten signature in black ink, appearing to read 'John Sutter', written in a cursive style.

John Sutter  
City Planner/Assistant Community Development Director

**PROPOSAL FORM**  
**PROPOSAL TO THE ECONOMIC DEVELOPMENT AUTHORITY OF THE CITY OF CRYSTAL**  
**4343 XENIA AVENUE NORTH**

**CHECK ONE:**

- BUILDER OFFERS \$50,000 TO PURCHASE THIS LOT**
- BUILDER OFFERS \$500 FOR A SIX-MONTH OPTION TO PURCHASE THIS LOT FOR \$50,000**

This proposal is not a purchase agreement or other binding contract. At this time, the Builder is submitting a proposal to purchase this lot and build a new single family house in accordance with the RFP Guidelines, or is requesting a six-month option for same.

If a builder's proposal is tentatively accepted by the EDA board, then EDA staff would work with the Builder to determine the specific house plan and present it at the next EDA meeting. If the EDA board gives final approval at that time, the Builder would sign a Purchase & Redevelopment Agreement and provide \$2,000 earnest money for the lot. Only after such an Agreement is signed would a binding contract exist between the EDA and the Builder.

Builders may purchase a 6-month option on a lot for \$500, renewable for an additional 6 months for an additional \$500. The option provides the builder with exclusive rights to purchase the lot and build a house subject to the normal EDA process, requirements and guidelines. As a condition of the option, the builder must list the lot with a to-be-built house on the MLS for the duration of the option. The number of options is limited: No builder may have options on more than 10% of the EDA's lots, and no more than 50% of the EDA's lots may be under option at any time.

**BUILDER:** *(Builder is required to be a Residential Building Contractor licensed by the State of Minnesota.)*

Name: \_\_\_\_\_ State License Number: \_\_\_\_\_

Tel (1): \_\_\_\_\_ Tel (2): \_\_\_\_\_ Fax: \_\_\_\_\_

Address: \_\_\_\_\_ City/State/Zip: \_\_\_\_\_

Email: \_\_\_\_\_

Signature \_\_\_\_\_ Date \_\_\_\_\_

**REQUIRED ATTACHMENTS AND ADDITIONAL INFORMATION:**

- Attach one representative example of a house you would plan to build on this lot if your proposal is selected. It does not need to show exactly how it would be placed on the lot; it just needs to show the approximate size, quality and features you would anticipate a new house would have on this lot. A specific house plan would be determined after a proposal is tentatively accepted by the EDA.
- The EDA will only sell lots to builders who have experience in house construction in Minnesota. Please list the addresses of three houses you have built in Minnesota within the last five years, or attach other evidence of qualification for review by the EDA:

House #1: \_\_\_\_\_

House #2: \_\_\_\_\_

House #3: \_\_\_\_\_

**SUBMIT PROPOSAL TO:** Attn: John Sutter, Crystal EDA, 4141 Douglas Dr N, Crystal MN 55422  
TEL: 763.531.1142 FAX: 763.531.1188 [john.sutter@crystalmn.gov](mailto:john.sutter@crystalmn.gov)

**PROPOSALS MAY BE SUBMITTED BY HAND DELIVERY, U.S. MAIL, FAX, OR EMAIL (.pdf format).  
PROPOSALS MAY BE SUBMITTED AT ANY TIME AND WILL BE CONSIDERED ON A "FIRST COME,  
FIRST SERVED" BASIS UNLESS THE LOT HAS BEEN OPTIONED BY ANOTHER BUILDER.**

## **RFP GUIDELINES FOR 4343 XENIA AVENUE NORTH**

- A. Legal Description.** The property is legally described as: Lot 5, Block 3, Robbinsdale Home Gardens Third Addition
- B. Anticipated Timeline for Lot Sales.**  
After a builder submits a qualifying proposal, the timeline would be as follows:
- EDA meeting #1: EDA rejects or tentatively accepts Builder's proposal. If accepted, Builder prepares detailed house plans for EDA public hearing.
  - EDA meeting #2 (approximately one month after #1): EDA holds public hearing and considers a resolution authorizing the lot sale.
  - 10 days after EDA meeting #2: Deadline for Builder to sign the Purchase & Redevelopment Agreement and pay \$2,000 nonrefundable earnest money.
  - 2 months after EDA meeting #2: Deadline for Builder to close on the lot purchase.
- C. Deadline for Completion.** Construction of the new house must be completed within one year of EDA meeting #2 (see above).
- D. Specifications.**
- 1. Grading and Drainage.**
    - a) The lot is essentially level, with a slight drop from southwest to northeast. The estimated top of foundation would be 883 feet. This elevation would be refined by Builder and EDA staff during the development of specific house plans prior to final EDA approval of the lot sale. Upon completion of the final grade but prior to installing landscaping, Builder shall submit an as-built survey to the Building Official showing the final grade elevations, unless EDA staff determines that it is not necessary.
    - b) Drainage from the house, garage, driveway and any other structures shall be accommodated on the site so that water flow onto adjacent properties is minimized. Builder's final grade shall carry water to the street and alley, not adjacent properties to the north and south. If determined by the Building Official to be necessary, Builder will install rain gutters to direct roof runoff to minimize impacts on adjacent properties. Builder will restore any disturbed turf or landscaping.
    - c) Builder will follow Best Management Practices to minimize erosion and runoff onto adjacent properties and public ways. At a minimum, Builder will install silt fencing or wattle logs to prevent runoff silt from flowing onto the street or adjacent properties.
  - 2. Utilities.**
    - a) Utility meters shall be reasonably screened from street view; locations must be specified on the plans submitted with the building permit application.
    - b) All utility service lines shall be underground. Utilities may locate necessary facilities such as pedestals or boxes in the street right-of-way or utility & drainage easements.
    - c) Any expenses for connection of the house to utilities shall be the responsibility of Builder, including any necessary landscaping or sidewalk, curb or pavement work, but excepting reasonable costs associated with sewer stub replacement discussed in e) below.
    - d) Municipal Water. Municipal water is available at the lot line along Xenia using an existing service stub. There are no WAC charges.
    - e) Municipal Sanitary Sewer. Municipal sanitary sewer is available at the curb along Xenia using an existing service stub.

Upon exposure of the end of the sewer stub, Builder or its agents shall call the city's Utilities staff (763.531.1166) and have the stub and wye inspected before doing further work. If in poor condition, the city may require Builder to replace the stub to the wye. If such work is required, then the EDA will reimburse Builder for reasonable costs related to such work.

There are no SAC charges levied by Metropolitan Council Environmental Services.

- f) Private Utilities, including natural gas (Centerpoint Energy), electricity (Xcel Energy), telephone (Qwest), and cable television (Comcast). The house shall access private utilities via underground connections only.
    - Centerpoint is located in the street right-of-way.
    - Xcel, Qwest and Comcast are located on poles on the west side of the alley. No overhead connection to these utilities will be allowed. Builder shall work with the utilities to make an underground connection from the house to the utility pole, running under the alley.
  - g) Questions regarding city utilities should be directed to Engineering Project Manager Mick Cyert (763.531.1161 or [mick.cyert@crystalmn.gov](mailto:mick.cyert@crystalmn.gov)). Questions regarding private utilities should be directed to the respective utility company.
3. **Driveways and Curb Cuts.** A hard surfaced driveway is required to the house's garage. The house's building permit application, or garage building permit application if submitted separately, must include a site plan showing the proposed driveway layout. The driveway will access the alley.
4. **General Construction Practices.** The construction site, neighboring property and adjacent public streets shall be kept free of construction debris at all times, and Builder must have a construction dumpster to prevent debris from being scattered or blown around. No construction workers, construction equipment or construction material shall enter neighboring properties without said property owner's consent.
5. **Building Standards.**
- a) Compliance with Crystal City Code.
  - b) Minimum required setbacks for the house is as follows: 30 feet from the front lot line, 30 feet from the rear lot line, 5 feet from the side lot lines. City code does have some limited exceptions to the front and rear setbacks; those can be discussed in detail with EDA staff if your proposal is accepted.
  - c) The house shall have at least three bedrooms and two bathrooms.
  - d) The house shall have a full depth basement, unless the selected design results in a split level / garden level type of basement. At a minimum, basements shall have at least one egress window and a rough-in for a future ¼ bath. Additional basement windows are desirable. Slab houses and crawlspace houses will not be considered by the EDA.
  - e) Exterior materials (siding, soffit, doors and windows) shall be low maintenance. The use of brick or stucco is encouraged. Fiber cement siding or wood siding with natural resistance to decay are encouraged but they must be properly stained or painted. Vinyl or other low maintenance siding materials are generally acceptable and can be made more desirable through the use of shakes, fish scales or other styles to break up the pattern. Hardboard panels or hardboard lap siding are not acceptable.
  - f) The house shall have a detached garage for at least two cars and accessed from the alley via a hard surfaced driveway. If the garage directly faces the alley then it shall be set back at least 20 feet from the rear lot line along the alley. If the garage does not directly face the alley (i.e. side-loaded) then it shall be set back at least 3 feet from the

rear lot line along the alley. Eaves may extend into the 20 foot setback but not the 3 foot setback.

- g) The design should emphasize the front door as the focal point for the front of the house. Large and usable (minimum depth 6 feet) front porches are desired.
- h) Plans should present a balanced and pleasing distribution of wall and window areas from all views. Blank walls are not permitted; each wall shall have some windows. Corner rooms should have windows on both walls, if possible. To the extent that southern exposures are present, house designs are expected to enhance wintertime natural light and passive solar heating.
- i) The new house shall be built with a passive venting system for radon gas reduction.
- j) The new house shall have Carbon Monoxide alarms in accordance with M.S. 299F.50.
- k) No equipment such as air-conditioning cooling structures or condensers that generate noise shall be located within a side setback, drainage & utility easement, or 10 feet of living quarters located in a building on adjacent property.

**6. Landscaping.** The lot shall be landscaped to be aesthetically pleasing in all seasons. Land forms and plant materials shall be used to define the site and blend neatly with adjoining property.

At a minimum the following tree planting is required:

- in the front yard, one large-species deciduous shade tree; and
- in the rear yard, two large-species deciduous shade trees; and
- two ornamental trees in any yard.

Planting of the following trees is PROHIBITED:

- |                                    |   |
|------------------------------------|---|
| - <i>Acer ginnala</i>              | Amur maple  |
| - <i>Acer negundo</i>              | boxelder  |
| - <i>Acer platnoides</i>           | Norway maple                                      |
| - <i>A. saccharum</i>              | sugar maple                                       |
| - <i>A. sacharinum</i>             | silver maple                                      |
| - <i>A. rubrum</i>                 | red maple   |
| - <i>A. truncatum x platnoides</i> | hybrid maples eg. 'Aut.Blaze', 'Warrenseld', etc. |
| - <i>Fraxinus spp.</i>             | ash   |
| - <i>Morus spp.</i>                | mulberries  |
| - <i>Rhaqmnus spp.</i>             | buckthorns  |
| - <i>Populus spp.</i>              | poplars, cottonwoods, aspens                      |
| - <i>Robinia pseudoacacia</i>      | black locust                                      |
| - <i>Salix spp.</i>                | willows   |
| - <i>Tilia cordata</i>             | little-leaf linden                                |

Planting of the following trees is RECOMMENDED:

- |  |   |
|--|---|
| - <i>Aesculus spp.</i>                       | Horsechestnuts, Ohio buckeyes                 |
| - <i>Amelanchier arborea</i> , hybrids       | Downy serviceberry, 'Autumn Brilliance,' etc. |
| - <i>Betula nigra</i>                        | river birch                                   |
| - <i>Carpinus caroliniana</i>                | blue beech or musclewood                      |
| - <i>Celtis occidentalis</i>                 | common hackberry                              |
| - <i>Cercis Canadensis</i> 'Northern Strain' | 'Northern Strain' redbud                      |
| - <i>Cladrastus kentukea</i>                 | yellowwood                                    |
| - <i>Ginkgo biloba</i> , male cultivars      | ginkgo cultivars                              |
| - <i>Gleditsia triacanthos inermis</i>       | thornless honeylocust                         |
| - <i>Gymncladus dioecus</i>                  | Kentucky coffeetree                           |
| - <i>Ostrya virginiana</i>                   | ironwood                                      |
| - <i>Quercus alba</i>                        | white oak                                     |
| - <i>Q. bicolor</i>                          | swamp white oak                               |
| - <i>Q. macrocarpa</i>                       | bur oak                                       |

- *Q. rubrum* red oak
- *Syringa reticulata* tree lilac
- *Ulmus Americana* dis.resist vars. American elms, disease resistant
- *Ulmus hybrids* hybrid elms, disease resistant

Species, size and specific location of all new trees must be approved by City Forester James Burks (763.531.1162 or [james.burks@crystalmn.gov](mailto:james.burks@crystalmn.gov)). Builder must submit a planting plan to the City Forester for review and approval PRIOR TO PLANTING.

If Builder desires to close on the sale of the new house prior to completion and acceptance of the landscaping, the EDA may require that funds be escrowed by the Builder to guarantee that landscaping is completed in a timely manner after closing.

7. **Land Use and Property Tax Status.** The new house shall be a single-family, owner occupied house, and may not subsequently be taken off the property tax rolls.
8. **Special Requirements Related to Rain Garden in Front of the Property.** As part of the Phase 10 - Welcome Park Neighborhood Street Reconstruction Project, a rain garden was installed in the boulevard area along Xenia Avenue. Rain gardens are an alternative storm water treatment method that uses the natural filtration properties of certain plants and takes advantage of sandy soils in the project area. Builder shall protect the rain garden during construction, and shall not use the rain garden's small curb cut as an access point for the property. Upon purchasing the lot, Builder is solely responsible for rain garden preservation and maintenance. Upon sale of the property after the new house is completed, responsibility for preservation and maintenance of the rain garden will automatically transfer to the owner of the new house; and Builder is responsible for disclosing this obligation to the homebuyer prior to transfer of the property.

**E. Builder Selection Criteria.** Builders must meet the following requirements:

1. Licensed as a Residential Building Contractor by the State of Minnesota. Proposals submitted by parties not licensed as a Residential Building Contractor will not be considered by the EDA.
2. Have experience in house construction in Minnesota. Builders shall provide the addresses of three houses they have built in Minnesota within the last five years, or other evidence of qualification acceptable to the EDA.
3. Provide proof of Builder's risk, comprehensive general liability, and worker's compensation insurance coverage, if requested by EDA staff.
4. Provide references from previous customers, suppliers and inspectors, if requested by EDA staff.
5. Be capable of closing on the lot purchases within two months of the EDA approving the lot sale (EDA meeting #2).
6. Be capable of completing the houses within one year of the EDA approving the lot sale (EDA meeting #2).

**F. Procedure for Consideration of Builder Proposals.**

1. Builder proposals may be submitted at any time, and will be considered on a "first come, first served" basis. The EDA will only consider one proposal at a time.
2. EDA staff will review the proposal and present it to the EDA board at its next meeting.
3. At that meeting (EDA meeting #1), the EDA board will either reject or tentatively accept the proposal. If the proposal is accepted, then EDA staff will work with the builder to prepare detailed house plans for the lot. The EDA has total discretion regarding whether to reject or accept a proposal.

4. At its next meeting (EDA meeting #2), the EDA board will hold a public hearing and consider a resolution authorizing the sale of the lot to the Builder for construction of the house shown in the detailed plans.
5. No later than 10 days after EDA meeting #2, the Builder must sign the Purchase and Redevelopment Agreement and pay \$2,000 nonrefundable earnest money for the lot.
6. No later than 2 months after EDA meeting #2, the Builder must close on the sale of the lot. At closing, the Builder shall make full payment for the remainder of the lot price (the EDA does not provide interim financing). To save time, Builder may begin the building permit application process before the closing date. However, the permit will not be issued until Builder has closed on the lot.
7. No later than one year after EDA meeting #2, the Builder must complete the house.

**G. Building Permit Application Process.**



When applying for a building permit to construct the new house, Builder will need to provide a complete building permit application, including the following items:

- Plans (2 copies).
- Land Survey (2 copies) with building elevations, drainage patterns and easements.
- Energy Calculations.

Questions regarding building permit forms, fees, inspections, etc. should be directed to the Administration counter (763.531.1000). The Building Official and EDA staff will review all plans to assure conformance with Builder's proposal, these Guidelines and the house plan approved by the EDA. If any element of the plan is in conflict with the above criteria, EDA staff will notify Builder of any conflicts and note which changes are required. Unless the modifications can be clearly indicated on the originally submitted plans, Builder shall submit revised plans for final approval by the Building Official and EDA staff.

**H. List of Attachments:**

- 2009 aerial photo showing location of subject property
- Water tie card
- Sanitary sewer tie card
- Rain garden information
- Survey annotated with setback lines (May not be to scale due to reduction from 11"x17" to 8½"x11" paper. Hard copy of survey available upon request.)



# WATER SERVICE RECORD

FILE NO. 242050070

Address 4343 Xenia Ave N

Lot 5 Block 3 Plat ROBBINSPALE HOME GARDENS

MAIN: Location XENIA Size 6" Kind C.I.P. Depth \_\_\_\_\_ Soil \_\_\_\_\_  
(Street)

TAP: Size \_\_\_\_\_ Thread Type \_\_\_\_\_

CORP: Size \_\_\_\_\_ 1/8 Bend \_\_\_\_\_ Conn. \_\_\_\_\_ Make \_\_\_\_\_ Cat. No. \_\_\_\_\_  
(Yes-No) (Copper/Lead-Wipe)

SERVICE PIPE: (Corp to Curb Stop) Size \_\_\_\_\_ Kind \_\_\_\_\_ Depth \_\_\_\_\_ Length \_\_\_\_\_

CURB STOP: Size \_\_\_\_\_ Conn. \_\_\_\_\_ Make \_\_\_\_\_ Cat. No. \_\_\_\_\_  
(In) (Out)

Minn. Thd. \_\_\_\_\_ Invert. Key \_\_\_\_\_ Waste \_\_\_\_\_  
(Yes-No) (Yes-No) (Yes-No)


CURB BOX: Make \_\_\_\_\_ Size \_\_\_\_\_ Adjust. \_\_\_\_\_ Extension Rod \_\_\_\_\_  
(Slip-Screw-No) (Yes-No)

SERVICE PIPE: (Curb Stop to Bldg.) Size \_\_\_\_\_ Kind \_\_\_\_\_ Depth \_\_\_\_\_ Length \_\_\_\_\_

TAP LOCATION:

CURB BOX LOCATION:

Tapped By \_\_\_\_\_ Date 12/16/91 Permit No. 5082  
(Plumber)




# SANITARY SEWER SERVICE RECORD

1-13

Address: 4343 Xenia

Legal: LOT 5, BLK 3, ROBB HOME GARDENS 3RD ADDN

Permit No. 2407 Plumber *Andrews* Date Completed 10/10/57



Remarks: *Disconnected* 30' From Main Roots in line towards street.



4141 Douglas Drive North • Crystal, MN 55422-1696  
Telephone: (763) 531-1000 • Fax: (763) 531-1188  
Website: www.ci.crystal.mn.us

Date: April 23, 2009

What: Phase 10 Welcome Park Street Reconstruction Project –  
RAIN GARDEN QUESTIONNAIRE

To: Property Owners and Residents interested in having a Rain Garden, where one is  
viable, in the Public Boulevard in front of their home

From: City of Crystal and Short Elliott Hendrickson Inc.

---

Please complete and return this survey by U.S. mail, telephone, fax, or e-mail to Dave Fritzke,  
Crystal Engineering Department no later than Friday, May 15, 2008. All decisions on your  
completed questionnaire will be considered final on whether or not you wish to have the work  
done. Please see Dave's contact information at the end of this questionnaire.

Name(s): CRYSTAL EDA ECONOMIC DEVELOPMENT  
JOHN SUTTER - AUTHORITY OF THE  
CITY OF CRYSTAL

Address: 4141 DOUGLAS DR N

Phone #: (763) 531-1142(days)  
N/A (evenings)

### 1. Rain Garden Interest

Are you still interested in having a Rain Garden placed in the boulevard in front of your  
home?

Yes  No

- If you select "Yes" a rainwater garden will be constructed in the public boulevard in front of your home. Please continue to complete the questionnaire.
- If you select "No" a rainwater garden will not be constructed in front of your home. You may stop completing the questionnaire and return it to Dave Fritzke.
- *If you do not return your questionnaire, a rainwater garden will not be constructed in the boulevard in front of your home.*

### 2. Rain Garden Schedule

The Rain Garden construction will occur during street reconstruction this summer, beginning with Area A and ending with Area D (as shown on the location map of Street Reconstruction Newsletter No. 1 dated April 23, 2009). The Rain Garden planting will occur in the Spring or Summer of 2010. Several Rain Garden plant types will be made available to select from in the fall of 2009.

### 3. Rain Garden Planting

On planting day, staff will be available to demonstrate techniques and answer questions. Will you plant your own Rain Garden?

\_\_\_\_\_ Yes       No


- If you select "Yes", the contractor will supply the plants that you have selected. You must pick up the plants at a destination to be determined. A likely location may be the Crystal Community Center. You will be responsible for installing the plants and maintaining the rain garden.
- If you select "No" the contractor will supply and install the plants that you have selected. You will be responsible for maintaining the rain garden.

### 4. Other Questions or Comments

LOT IS VACANT BUT THE CRYSTAL EDA  
WILL BE SELLING IT FOR CONSTRUCTION  
OF A NEW SINGLE FAMILY HOUSE. THE NEW  
HOMEOWNER WILL ASSUME RESPONSIBILITY FOR THE  
RAIN GARDEN.

By signing below, the property owner agrees to the terms of the attached Rain Garden Maintenance document.

Signed



Date

5/07/2009

(FOR CRYSTAL EDA)

Please return this questionnaire in the enclosed envelope no later than Friday, May 15, 2009 to:

Dave Fritzke  
Crystal City Engineering Department  
4141 Douglas Drive N.  
Crystal, MN 55422

763.531.1163 (direct) 763.531.1188 (fax) [dave.fritzke@ci.crystal.mn.us](mailto:dave.fritzke@ci.crystal.mn.us)



4141 Douglas Drive North • Crystal, MN 55422-1696  
Telephone: (763) 531-1000 • Fax: (763) 531-1188  
Website: www.ci.crystal.mn.us

### RAIN GARDEN MAINTENANCE

1. The property owner agrees to the implementation of a rain garden in the public boulevard area adjacent to 4343 XENIA AVE N. The garden will be constructed by a Contractor, retained by the City.
2. The property owner agrees that the Contractor, its subcontractors, agents and employees, and employees of the City of Crystal, may enter the owner's private property for the purpose of carrying out such work activity as necessary to install the rain garden in the public boulevard area.

3. Yearly maintenance for weeding, mulching, and plant replacement will be conducted by the City of Crystal for a period of two years after the initial installation/planting.

- \* 4. The property owner agrees to perform basic maintenance activities according to the following schedule:

Year 1-2	Watering
Year 3 and beyond	Watering, weeding, mulching, and plant replacement as necessary.

p:\a\citycrystal\10767217\calnewsletters\rain garden\draft\design rain garden questionnaire.doc

↑  
**NEW HOMEOWNER  
SHALL BE INFORMED  
OF THIS BY BUILDER,  
NEW HOMEOWNER  
SHALL ACCEPT  
RESPONSIBILITY FOR  
MAINTENANCE.**

INVOICE NO. 77731  
 F.B. NO. 1042-73

Established in 1902  
**LOT SURVEYS COMPANY, INC.**  
 LAND SURVEYORS  
 REGISTERED UNDER THE LAWS OF THE STATE OF MINNESOTA  
 7061 7th Avenue North  
 Minneapolis, Minnesota 55425  
 (763) 561-3085  
 Fax No. 561-3022  
**Surveyors Certificate**

- Concrete Framed Iron Monument
- Cast-iron Monument
- x 000.0 Denotes Existing Elevation




Property located in Section 16, Township 118, Range 21, Hennepin County, Minnesota

**CRYSTAL ECONOMIC DEVELOPMENT AUTHORITY**

Property Address: 4943 Kenia Avenue North  
 plat number 16-118-21-21-0109

Benchmark: Top of Hydrant located at the NE corner of 7th St. & 4th Ave N  
 Elevation = 882.87 feet NGVD



Lot 5, Block 3, ROBINSDALE HOME GARDENS THIRD ADDITION,  
 Hennepin County, Minnesota.

The only easements shown are from plats of record or information provided by client.  
 We hereby certify that this is a true and correct representation of a survey of the boundaries of the above described land and the location of all buildings and visible encroachments, if any, from or on said land.

Surveyed by us this 6th day of December 2008.

*Gregory R. Prosch*

Signed  
 Gregory R. Prosch, Minn. Reg. No. 24992

Rev	Drawn By <i>addendum</i>
	File Name
	16-118-21-21-0109-77731.dwg