



4141 Douglas Drive North • Crystal, Minnesota 55422-1696

Tel: (763) 531-1000 • Fax: (763) 531-1188 • www.crystalmn.gov

REQUEST FOR PROPOSALS (“RFP”)

4720 Douglas Drive North Lot Price \$50,000

The Economic Development Authority of the City of Crystal (“the EDA”) is requesting proposals from builders to purchase 4720 Douglas Drive North for construction of a new single family house. Enclosed please find the Proposal Form and Guidelines for making a proposal.

To receive consideration, proposals must be submitted on a completed Proposal Form plus the required attachments and additional information. Incomplete proposals will not be considered. Proposals may be submitted at any time; the first qualifying proposal we receive will be presented to the EDA board, unless the lot has been optioned by another builder.

If you have questions about the RFP process or the enclosed Guidelines, feel free to contact me at 763.531.1142 or john.sutter@crystalmn.gov. Thank you for your interest.

Regards,

John Sutter
City Planner/Assistant Community Development Director

PROPOSAL FORM
PROPOSAL TO THE ECONOMIC DEVELOPMENT AUTHORITY OF THE CITY OF CRYSTAL
4720 DOUGLAS DRIVE NORTH

CHECK ONE:

___ **BUILDER OFFERS \$50,000 TO PURCHASE THIS LOT**

___ **BUILDER OFFERS \$500 FOR A SIX-MONTH OPTION TO PURCHASE THIS LOT FOR \$50,000**

This proposal is not a purchase agreement or other binding contract. At this time, the Builder is submitting a proposal to purchase this lot and build a new single family house in accordance with the RFP Guidelines, or is requesting a six-month option for same.

If a builder's proposal is tentatively accepted by the EDA board, then EDA staff would work with the Builder to determine the specific house plan and present it at the next EDA meeting. If the EDA board gives final approval at that time, the Builder would sign a Purchase & Redevelopment Agreement and provide \$2,000 earnest money for the lot. Only after such an Agreement is signed would a binding contract exist between the EDA and the Builder.

Builders may purchase a 6-month option on a lot for \$500, renewable for an additional 6 months for an additional \$500. The option provides the builder with exclusive rights to purchase the lot and build a house subject to the normal EDA process, requirements and guidelines. As a condition of the option, the builder must list the lot with a to-be-built house on the MLS for the duration of the option. The number of options is limited: No builder may have options on more than 10% of the EDA's lots, and no more than 50% of the EDA's lots may be under option at any time.

BUILDER: *(Builder is required to be a Residential Building Contractor licensed by the State of Minnesota.)*

Name: _____ State License Number: _____

Tel (1): _____ Tel (2): _____ Fax: _____

Address: _____ City/State/Zip: _____

Email: _____
Signature _____ Date _____

REQUIRED ATTACHMENTS AND ADDITIONAL INFORMATION:

- Attach one representative example of a house you would plan to build on this lot if your proposal is selected. It does not need to show exactly how it would be placed on the lot; it just needs to show the approximate size, quality and features you would anticipate a new house would have on this lot. A specific house plan would be determined after a proposal is tentatively accepted by the EDA.
- The EDA will only sell lots to builders who have experience in house construction in Minnesota. Please list the addresses of three houses you have built in Minnesota within the last five years, or attach other evidence of qualification for review by the EDA:

House #1: _____

House #2: _____

House #3: _____

SUBMIT PROPOSAL TO: **Attn: John Sutter, Crystal EDA, 4141 Douglas Dr N, Crystal MN 55422**
TEL: 763.531.1142 FAX: 763.531.1188 john.sutter@crystalmn.gov

**PROPOSALS MAY BE SUBMITTED BY HAND DELIVERY, U.S. MAIL, FAX, OR EMAIL (.pdf format).
PROPOSALS MAY BE SUBMITTED AT ANY TIME AND WILL BE CONSIDERED ON A "FIRST COME,
FIRST SERVED" BASIS UNLESS THE LOT HAS BEEN OPTIONED BY ANOTHER BUILDER.**

RFP GUIDELINES FOR 4720 DOUGLAS DRIVE NORTH

- A. Legal Description.** The property is legally described as the North 60 feet of the West 225 feet of the South 300 feet of Southwest ¼ of Northwest ¼ of Southwest ¼ of Section 9, Township 118, North Range 21, West of the 5th Principal Meridian, Hennepin County, Minnesota, excluding road.
- B. Anticipated Timeline for Lot Sales.**
After a builder submits a qualifying proposal, the timeline would be as follows:
- EDA meeting #1: EDA rejects or tentatively accepts Builder's proposal. If accepted, Builder prepares detailed house plans for EDA public hearing.
 - EDA meeting #2 (approximately one month after #1): EDA holds public hearing and considers a resolution authorizing the lot sale.
 - 10 days after EDA meeting #2: Deadline for Builder to sign the Purchase & Redevelopment Agreement and pay \$2,000 nonrefundable earnest money.
 - 2 months after EDA meeting #2: Deadline for Builder to close on the lot purchase.
- C. Deadline for Completion.** Construction of the new house must be completed within one year of EDA meeting #2 (see above).
- D. Specifications.**
- 1. Grading and Drainage.**
 - a) The lot is generally level. Estimated top of foundation for the new house would be 879 feet. The elevation would be refined by Builder and EDA staff during the development of the specific house plan prior to final EDA approval of the lot sale. Upon completion of the final grade but prior to installing landscaping, Builder shall submit an as-built survey to the Building Official showing the final grade elevations, unless EDA staff determines that it is not necessary.
 - b) Drainage from the house, garage, driveway and any other structures shall be accommodated on the site so that water flow onto adjacent properties is minimized. Builder's final grade shall carry water primarily to Douglas Drive or the swale on the Crystal Community Center property directly to the north. If determined by the Building Official to be necessary, Builder will install rain gutters to direct roof runoff to minimize impacts on adjacent properties. Builder will restore any disturbed turf or landscaping.
 - c) Builder will follow Best Management Practices to minimize erosion and runoff onto adjacent properties and public ways. At a minimum, Builder will install silt fencing or wattle logs to prevent runoff silt from flowing onto the street or adjacent properties.
 - 2. Utilities.**
 - a) Utility meters shall be reasonably screened from street view; locations must be specified on the plans submitted with the building permit application.
 - b) All utility service lines shall be underground. Utilities may locate necessary facilities such as pedestals or boxes in the street right-of-way or utility & drainage easements.
 - c) Any expenses for connection of the house to utilities shall be the responsibility of Builder, including any necessary landscaping or sidewalk, curb or pavement work, but excepting reasonable costs associated with sewer stub replacement discussed in e) below.
 - d) Municipal Water. Municipal water is available at, or east of, the sidewalk along Douglas Drive using an existing service stub. There are no WAC charges.

- e) Municipal Sanitary Sewer. Municipal sanitary sewer is available at, or east of the sidewalk along Douglas Drive using an existing sewer service stub. There are no SAC charges levied by Metropolitan Council Environmental Services.
- f) Private Utilities, including natural gas (Centerpoint Energy), electricity (Xcel Energy), telephone (Century Link), and cable television (Comcast). The house shall access private utilities via underground connections only.
- g) Questions regarding city utilities should be directed to Engineering Project Manager Mick Cyert (763.531.1161 or mick.cyert@crystalmn.gov). Questions regarding private utilities should be directed to the respective utility company.

3. Driveways and Curb Cuts.

- A hard surfaced driveway is required to provide access from the street to the new house's garage.
- The driveway must tie into and match the existing 22 foot wide curb cut on Douglas Drive.
- The house's building permit application must include a site plan showing the proposed driveway layout.

4. General Construction Practices. The construction site, neighboring property and adjacent public streets shall be kept free of construction debris at all times, and Builder must have a construction dumpster to prevent debris from being scattered or blown around. No construction workers, construction equipment or construction material shall enter neighboring properties without said property owner's consent.

5. Building Standards.

- a) Compliance with Crystal City Code.
- b) Minimum required setbacks for the house are as follows: 40 feet* from the front lot line, 30 feet from the rear lot line; and 5 feet from the side lot lines**. City code does have some limited exceptions to the front and rear setbacks for small bump-outs, porches and decks; those can be discussed in detail with EDA staff if your proposal is accepted.
 - * *The minimum front setback required by the zoning ordinance is 30 feet. However, the EDA is imposing a minimum 40 foot setback to match the setback of the adjacent house at 4716 Douglas Dr.*
 - ** *In the case of the north side lot line, the side setback is controlled by a 5 foot drainage & utility easement. No part of any building may be located within, under or over this easement; for example, if the house's roof has a 1 foot eave/overhang, then the foundation wall must be at least 6 feet from the north side lot line.*
- c) The house shall have at least three bedrooms and two bathrooms.
- d) The house shall have a full depth basement, unless the selected design results in a split level / garden level type of basement. At a minimum, basements shall have at least one egress window and a rough-in for a future ¾ bath. Additional basement windows are desirable. Slab houses and crawlspace houses will not be considered by the EDA.
- e) Exterior materials (siding, soffit, doors and windows) shall be low maintenance. The use of brick or stucco is encouraged. Fiber cement siding or wood siding with natural resistance to decay are encouraged but they must be properly stained or painted. Vinyl or other low maintenance siding materials are generally acceptable and can be made more desirable through the use of shakes, fish scales or other styles to break up the pattern. Hardboard panels or hardboard lap siding are not acceptable.
- f) The house shall have an attached garage for at least two cars, accessed via a hard surfaced driveway from Douglas Drive.

- g) The design should emphasize the front door as the focal point for the front of the house. A large and usable (minimum depth 6 feet) front porch is desired. Garage door dominance in design should be minimized as much as possible, such as by using separate doors for each stall.
- h) Plans should present a balanced and pleasing distribution of wall and window areas from all views. Blank walls are not permitted; each wall shall have some windows. Corner rooms should have windows on both walls, if possible. To the extent that southern exposures are present, house designs are expected to enhance wintertime natural light and passive solar heating.
- i) The new house shall be built with a passive venting system for radon gas reduction.
- j) The new house shall have Carbon Monoxide alarms in accordance with M.S. 299F.50.
- k) No equipment such as air-conditioning cooling structures or condensers that generate noise shall be located within a side setback, drainage & utility easement, or 10 feet of living quarters located in a building on adjacent property.

6. Landscaping. The lot shall be landscaped to be aesthetically pleasing in all seasons. Land forms and plant materials shall be used to define the site and blend neatly with adjoining property.

At a minimum the following tree planting is required:

- Plant one large-species deciduous shade tree in the front yard; and
- Plant one large-species deciduous shade tree and one ornamental tree in the rear yard; and
- If removing or damaging any existing tree having a diameter in excess of 6 inches, then plant one compensating tree (to be determined by the City Forester).

Planting of the following trees is PROHIBITED:

- | | |
|------------------------------------|--|
| - <i>Acer ginnala</i> | Amur maple |
| - <i>Acer negundo</i> | boxelder |
| - <i>Acer platnoides</i> | Norway maple |
| - <i>A. saccharum</i> | sugar maple |
| - <i>A. sacharinum</i> | silver maple |
| - <i>A. rubrum</i> | red maple |
| - <i>A. truncatum x platnoides</i> | hybrid maples eg. 'Aut.Blaze', 'Warrensed', etc. |
| - <i>Fraxinus spp.</i> | ash |
| - <i>Morus spp.</i> | mulberries |
| - <i>Rhaqmnus spp.</i> | buckthorns |
| - <i>Populus spp.</i> | poplars, cottonwoods, aspens |
| - <i>Robinia pseudoacacia</i> | black locust |
| - <i>Salix spp.</i> | willows |
| - <i>Tilia cordata</i> | little-leaf linden |

Planting of the following trees is RECOMMENDED:

- | | |
|--|---|
| - <i>Aesculus spp.</i> | Horsechestnuts, Ohio buckeyes |
| - <i>Amelanchier arborea</i> , hybrids | Downy serviceberry, 'Autumn Brilliance,' etc. |
| - <i>Betula nigra</i> | river birch |
| - <i>Carpinus caroliniana</i> | blue beech or musclewood |
| - <i>Celtis occidentalis</i> | common hackberry |
| - <i>Cercis Canadensis</i> 'Northern Strain' | 'Northern Strain' redbud |
| - <i>Cladrastus kentukea</i> | yellowwood |
| - <i>Ginkgo biloba</i> , male cultivars | ginkgo cultivars |
| - <i>Gleditsia triacanthos inermis</i> | thornless honeylocust |
| - <i>Gymncladus dioecus</i> | Kentucky coffeetree |
| - <i>Ostrya virginiana</i> | ironwood |
| - <i>Quercus alba</i> | white oak |
| - <i>Q. bicolor</i> | swamp white oak |

- *Q. macrocarpa* bur oak
- *Q. rubrum* red oak
- *Syringa reticulata* tree lilac
- *Ulmus Americana* dis.resist vars. American elms, disease resistant
- *Ulmus hybrids* hybrid elms, disease resistant

Species, size and specific location of all new trees must be approved by City Forester James Burks (763.531.1162 or james.burks@crystalmn.gov). Builder must submit a planting plan to the City Forester for review and approval PRIOR TO PLANTING.

If Builder desires to close on the sale of the new house prior to completion and acceptance of the landscaping, the EDA may require that funds be escrowed by the Builder to guarantee that landscaping is completed in a timely manner after closing.

7. **Land Use and Property Tax Status.** The new house shall be a single-family, owner occupied house, and may not subsequently be taken off the property tax rolls.
8. **ADVISORY: Potential New Entrance to Crystal Community Center Parking Lot. The city is contemplating the construction of an entrance from Douglas Drive to the Crystal Community Center parking lot directly north of the Property. At this time it is uncertain if or when this work would occur. If it does occur, the work would likely be similar to what is shown in red on the attached concept sketch. The exact details of the work are subject to change if or when the city decides to proceed with the work.**

E. Builder Selection Criteria. Builders must meet the following requirements:

1. Licensed as a Residential Building Contractor by the State of Minnesota. Proposals submitted by parties not licensed as a Residential Building Contractor will not be considered by the EDA.
2. Have experience in house construction in Minnesota. Builders shall provide the addresses of three houses they have built in Minnesota within the last five years, or other evidence of qualification acceptable to the EDA.
3. Provide proof of Builder's risk, comprehensive general liability, and worker's compensation insurance coverage, if requested by EDA staff.
4. Provide references from previous customers, suppliers and inspectors, if requested by EDA staff.
5. Be capable of closing on the lot purchase within two months of the EDA approving the lot sale (EDA meeting #2).
6. Be capable of completing the house within one year of the EDA approving the lot sale (EDA meeting #2).

F. Procedure for Consideration of Builder Proposals.

1. Builder proposals may be submitted at any time, and will be considered on a "first come, first served" basis. The EDA will only consider one proposal at a time.
2. EDA staff will review the proposal and present it to the EDA board at its next meeting.
3. At that meeting (EDA meeting #1), the EDA board will either reject or tentatively accept the proposal. If the proposal is accepted, then EDA staff will work with the builder to prepare detailed house plans for the lot. The EDA has total discretion regarding whether to reject or accept a proposal.
4. At its next meeting (EDA meeting #2), the EDA board will hold a public hearing and consider a resolution authorizing the sale of the property to the Builder for construction of the house shown in the detailed plans.

5. No later than 10 days after EDA meeting #2, the Builder must sign the Purchase and Redevelopment Agreement and pay \$2,000 nonrefundable earnest money.
6. No later than 2 months after EDA meeting #2, the Builder must close on the sale of the lot. At closing, the Builder shall make full payment for the remainder of the lot price (the EDA does not provide interim financing). To save time, Builder may begin the building permit application process before the closing date. However, the permit will not be issued until Builder has closed on the lot.
7. No later than one year after EDA meeting #2, the Builder must complete the house.

G. Building Permit Application Process.


When applying for a building permit to construct the new house, Builder will need to provide a complete building permit application, including the following items:

- Plans (2 copies).
- Land Survey (2 copies) with building elevations, drainage patterns and easements.
- Energy Calculations.

Questions regarding building permit forms, fees, inspections, etc. should be directed to the Administration counter (763.531.1000). The Building Official and EDA staff will review all plans to assure conformance with Builder's proposal, these Guidelines and the house plan approved by the EDA. If any element of the plan is in conflict with the above criteria, EDA staff will notify Builder of any conflicts and note which changes are required. Unless the modifications can be clearly indicated on the originally submitted plans, Builder shall submit revised plans for final approval by the Building Official and EDA staff.

H. List of Attachments:

- 2012 aerial photo showing location of subject property
- Water tie card
- Sanitary sewer tie card
- Concept sketch showing possible new entrance to adjacent Crystal Community Center parking lot north of the subject property
- Survey with setback lines and other site information (May not be to scale due to reduction from 11"x17" to 8½"x11" paper. Hard copy of survey available upon request.)



Parcel ID: 09-118-21-32-0005

Owner Name: City Of Crystal

Parcel Address: 4720 Douglas Dr N
Crystal, MN 55429

Property Type: Residential

Home-stead: Non-Homestead

Parcel Area: 0.26 acres
11,476 sq ft

A-T-B: Abstract

Market Total: \$0

Tax Total: \$0.00
(Payable: 2013)

Sale Price: \$31,198

Sale Date: 03/2012

Sale Code:

Map Scale: 1" ≈ 50 ft.

Print Date: 10/23/2013



This map is a compilation of data from various sources and is furnished "AS IS" with no representation or warranty expressed or implied, including fitness of any particular purpose, merchantability, or the accuracy and completeness of the information shown.

COPYRIGHT © HENNEPIN COUNTY 2013



WATER SERVICE RECORD

FILE NO. 2-39-0320-60

Address 4720 Douglas Drive N

Lot (3503) Block _____ Plat S 1/2 SEC. 9,

MAIN: Location DOUGLAS DR Size 30" Kind PCCP Depth _____ Soil _____

TAP: Size 1" Thread Type AWWA

CORP: Size 1" 1/8 Bend Yes Conn. C Make Mueller Cat. No. H-15010
(Yes-No) (Copper-Lead-Wipe)

SERVICE PIPE: (Corp to Curb Stop) Size 1" Kind C Depth _____ Length _____

CURB STOP: Size 1" Conn. 1" Make Mueller Cat. No. H-15151
(In) (Out)

Minn. Thd. Yes Invert. Key No Waste No
(Yes-No) (Yes-No) (Yes-No)


CURB BOX: Make Mueller Size 1 1/4" Adjust. Slip Extension Rod No
(Slip-Screw-No) (Yes-No)

SERVICE PIPE: (Curb Stop to Bldg.) Size 1" Kind C Depth _____ Length _____

TAP LOCATION: _____ CURB BOX LOCATION: _____

Tapped By _____ Date 7/14/78 Permit No. 360
(Plumber)

HYD. 47th AVENUE




SANITARY SEWER

7-46 B

Address: 4720 Douglas Drive

Legal: Part of 051444-5 8th Add.

Permit No. 379 of Plumber Perry Date Completed 4-7-59




6+63 ● 47TH AVE

Remarks:

The Gregory Group
d.b.a.

LOT SURVEYS COME
Established in 1962
LAND SURVEY
REGISTERED UNDER THE LAWS OF STATE
7601 73rd Avenue North
Minneapolis, Minnesota 55428
Surveyors

EXISTING CONDITIONS SURVEY FOR:
CITY OF CRYSTAL ECONOMIC & DEVELOPMENT AUTHORITY



The West 225 feet of the North 60 feet of the South 300 feet of the Northwest Quarter Southwest Quarter of Section 9, Township 118, Range 21, Hennepin County, Minnesota Subject to Douglas Drive. Subject to easement and restrictions of record, if any.

The Gregory Group
d.b.a.

LOT SURVEYS COMPANY, INC.

Established in 1962

LAND SURVEYORS

REGISTERED UNDER THE LAWS OF STATE OF MINNESOTA

7601 73rd Avenue North
Minneapolis, Minnesota 55428

(763) 560-3093
Fax No. 560-3522

Surveyors Certificate

INVOICE NO. 79945

F.B.NO. 1056-72

SCALE: 1" = 20'

- Denotes Found Iron Monument
- Denotes Iron Monument

x000.0 Denotes Existing Elevation


Benchmark: Top nut of hydrant at Douglas Drive and 45th Ave. N.
Elevation = 881.14 feet

EXISTING CONDITIONS SURVEY FOR:

CITY OF CRYSTAL ECONOMIC & DEVELOPMENT AUTHORITY

Property address: 4720 Douglas Drive N. Crystal, MN

W 1/4 corner, Sec. 9
Henn. Co. Monument



Basis of bearings is based on Hennepin Co. County Coordinates.



DOUGLAS DRIVE N.
(Co. Road No. 102 - Plat 22)

* Drainage & Utility Easements

Setback Lines

bituminous parking lot

1-Story Frame No. 4716

1-Story Frame No. 4720

1-Story Stucco Garage/Shop

Frame Garage

The only easements shown are from plats of record or information provided by client.

I certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed land Surveyor under the laws of the State of Minnesota Surveyed this 3rd day of February 2012.

Signed *Gregory R. Prasch*
Gregory R. Prasch, Minn. Reg. No. 24992

The West 225 feet of the North 60 feet of the South 300 feet of the Northwest Quarter of the Southwest Quarter of Section 9, Township 118, Range 21, Hennepin County, Minnesota.
Subject to Douglas Drive. Subject to easement and restrictions of record, if any.

| | |
|-----|------------------------------------|
| Rev | Drawn By DJB |
| | File Name |
| | 9-118-21-nw-swfb105672inv79945.dwg |